



# Psi Value ( $\Psi$ ) Calculations & Report

CERTIFICATE REF:  
HTP-100F-0.033-1.33

### External wall construction including Hi-therm Lintel:

<b>CAVITY WIDTH</b> 100mm	<b>CAVITY INSULATION TYPE</b> Pumped Bead
<b>CAVITY INSULATION FILL</b> Full	<b>BLOCK TYPE</b> Dene Block

**Psi Value ( $\psi$ )**  
**0.051**  
(W/mK)

### Material Thermal Conductivities (W/mK)

Material	Thickness (mm)	Conductivity (W/mK)
External Brick	100	0.770
Pumped Bead	100mm	0.033
Dense Block	100	1.33
Plaster Dabs & Air space	10	0.066
Plaster Board	12.5	0.190



**Temperature Factor**  
**f = 0.909**  
(DEFAULT 0.75)



**U Value**  
**0.272**  
(W/m<sup>2</sup>K)

This report was carried out using Physibel Trisco thermal analysis software and the modeling follows the conventions set out for calculating linear thermal transmittance and temperature factors in accordance with BR497.

